



**TRAFFIC MANAGEMENT NOTES:**  
1) All temporary traffic management shall be in accordance with Chapter 8 of the Traffic Signs Manual.  
2) All temporary traffic management shall be in accordance with the Traffic Signs Regulations and General Directions 2016.  
3) All temporary traffic management shall conform to the Safety at Street Works and Road Works, A Code of Practice.  
4) All signing should be located 450mm minimum from any carriageway.  
5) All temporary traffic management sign locations are indicative and are subject to on site approval from the Engineer.

**Traffic control by 'Temporary obstruction' sign**  
This sign may be placed in advance of the works if all the following apply:  
• no alternative method of operation is practicable;  
• other forms of temporary traffic management are not practicable;  
• the highway authority is notified in advance and agrees to the expected use of this measure;  
• traffic is delayed for no more than 15 minutes at any one time, and there is at least one hour between such delays;  
• the 'Temporary obstruction' sign is placed within sight of the obstruction; and  
• the activities and the method of operation are such that operatives can reopen the road immediately for emergency purposes or on request from an appropriate authority.

**Key**

- Traffic sign
- Traffic cone
- Pedestrian barrier

Checked by: S.Smith	
Customer:	
Job reference:	
Location: Carmarthen	QR Code:
Date: 11/11/2025	
Description: Temporary Obstruction 15 Minutes Delay	
Scale: NTS	OS HA:
0330 043 3030 www.corehighways.com	
Produced by: D. Wall	
Design reference: 001	